



Work Packaging Versus WorkFace Planning

COAA WorkFace Planning Conference
September 20, 2011

Tannis Liviniuk, Cenovus Energy
Scott Wilson, JV Driver





Welcome

- Introductions
- Today's objective
- Yeah No




What is Work Packaging?

- Work packaging is the division or breakdown of Construction Work Packages (CWP's) into smaller manageable chunks of work
- Primarily discipline specific
- Often completed by the General Foremen
- Simply sequenced
- Little or no interdependent planning between trades to sequence work
- Not a controlled document (exist as field packages)

Why Package Work?

- It is difficult for Foremen to execute a CWP in its entirety due to the large scope and many possible execution strategies
- Crew productivity averages 35-40% time on tools
- Allows a definitive breakdown of manageable work 'chunks'
- CWP's are sometimes incomplete / unclear, therefore packaging identifies missing documentation / information
- Allows the General Foreman to sequence packages rather than tasks
- Provides an easy to use collection of required drawings for crews

Average Crew Activity Time



Tool Time
 Crew Movement
 Crew Planning


Wait Time
 Early Quits / Breaks
 Eq/Mat Movement

Concerns with Work Packaging

- There is often little or no sequencing of work packages
- Often these packages are not integrated with schedule sequencing (disconnected from project controls)
- Rarely reviewed and signed off by foremen, quality control or HSE personnel
- Order of issue may not reflect the path of construction
- Not easily progressable
- Little or no focus on constraint satisfaction
- Minimal traceability


Audience Question

- The most difficult constraint to manage on our projects has been:
 - a) Material availability
 - b) Work force density / Access to area
 - c) Scaffold completion
 - d) Availability of equipment
 - e) Availability of labour
 - f) Engineered drawings (availability or revisions)



Material Management

- Work Packaging places little emphasis on managing constraints, including materials
- Although the package has been issued to the foreman, rarely has anyone verified that the materials are all available.
- This places the burden on the foreman to verify the availability of materials.
- If the materials are not available, plans must change on the fly and alternative work tasks must be sourced.
- This causes downtime for the crew, which inevitably increases the total installed cost of a project.



Did you know?

"A \$2.5 billion mega-project in Alberta required 3.5 million person hours of engineering and 15 million construction hours. Between 40,000 and 50,000 design drawings and 10,000-20,000 vendor and shop drawings were also needed."

~ Colwell, 2008



Documentation Management

- Work Packaging inherently limits efficiency in managing drawing revisions or additions.
- As these packages are not controlled, and there is often no master copy of the package, document management becomes difficult and untraceable.
- Revisions may be released and not make it to the field
- This creates the potential for extensive amounts of rework





COAA
Construction Owners
Association of Alberta





A Comprehensive Approach

- FIWP's are electronically packaged early in engineering (EDS)
- FIWP's are packaged according to an FIWP release plan developed at the end of the DBM stage
- This plan is developed to reflect that path of construction developed during DBM
- The path of construction is determined early to ensure alignment with the path of engineering
- Constraints are constantly monitored, and if cannot be satisfied tasks may be moved to another FIWP
- Package content is vetted by construction teams and stake holders



FIWP's & Project Management

- Stake holders include; Safety, Schedule, Project controls, QAQC, Turnover, Hydro Testing, Materials, Change management, Construction Management and Document Control
- During FIWP development BOM's are created based on drawings and details and issued to the materials group by the construction coordinator/Workface planner
- The BOM's are utilized to gather, bag and tag materials per FIWP
- Confirmation of material availability is then sent to the WorkFace Planning group
- Tasks within an FIWP may be redistributed if material availability does not support the FIWP release date
- Release of the FIWP complete with IFC drawings is based on being ready

Differences

Work Packaging

- No requisite mhrs
- Not integrated with project controls
- Not monitored and controlled for progress
- Contains engineered drawings and other documentation from the CWP

WorkFace Planning

- 500 – 1000 man hours
- Integration with project controls
- Monitored and controlled
- Contains all documentation that a foreman requires to complete the work

Differences

Work Packaging

- Material not controlled to package
- Packages are often built without planning for contingencies
- Packages built by Foreman or General Foreman

WorkFace Planning

- Materials bagged and tagged per FIWP
- Contingency packages are built to cover plans B & C
- FIWP's built by dedicated WorkFace Planner with General Foreman
- Completed FIWP's are transferred to QAQC Complete with Red lines





Audience Question

- Does your organization utilize:
 - a) Work Packaging
 - b) WorkFace Planning
 - c) Both systems on different projects
 - d) Other
 - e) I am not employed with an organization that executes construction projects



Audience Question

- Does the method you utilize depend on the project size?
 - a) Yes
 - b) No
 - c) We only use one method
 - d) We don't use either method



Audience Question

- What roadblocks does your organization face in the use of a work packaging or workface planning system ?
 - A) Good Ol' Boy mentality – we've done it this way for 30 years, why change it?
 - B) Unmanageability of package monitoring and control
 - C) Shortage of skilled trades people to package work
 - D) Lack of information sharing
 - E) Undefined or poorly defined packaging processes
 - F) Poor training of craft / supervision / management
 - G) Engineering revisions

Audience Question

- The most significant benefit that I feel may be achieved by my organization through the use of WorkFace Planning is:
 - a) Increased craft productivity
 - b) Improved safety performance
 - c) Better morale within supervision
 - d) Better efficiency of integrated systems
 - e) Better organizational collaboration

