

Productivity Analysis and Management

**If you Measure It
They will come**

Case Study: Advanced Work Packaging and Tool Time Analysis

- North American Project
- \$5 Billion
- 2 Year above ground schedule
- Advanced Work Packaging
- Tool Time Activity Analysis

AWP Procedure


Comprehensive Procedure (60 Pages)

Flow charts

Templates

Job Descriptions


Definitions




Methodology

- Trained Observers, from Construction
- Detailed Standard Procedure
- Random Patterns
- Balanced calls across Hours and Areas
- 000's of Observations per Survey

Tool Time Analysis



Tool Time by Trade



Tool Time



Trade Workers



Productivity Analyst

Observations




Access Database

Weekly Report

Activity



Planning



Area CMT

Action Items



Workforce Planner

Progress



Trade Workers



WFP Analyst

Scorecard
& Report
for each Area (8)

Chair



Area Steering Committee



Workface Planning Compliance

Sample size

- 5 Companies
- 8 Unique areas
- 5000 workers
- 8 Months
- 2 Cycles each
- 80,000 observations


Compliance with AWP

- Detailed procedure issued with the contract
- Contractors left to interpret and apply the process
- Interviews and **AWP scorecard** used to measure compliance
- No companies achieved substantial compliance with 'constraint free' or short duration (1 week) IWPs.



The True Influence of Advanced Work Packaging

% of Compliance with AWP



Tool Time

AWP Attributes


- Best in Class Contractor:
 - Workface Planners had Construction Expertise.
 - 1 to 50 ratio
 - SmartPlant Construction
 - Engineering and Procurement alignment
- Worst Performing Contractor:
 - Summer Students developing Packages
 - 1- 200 Ratio
 - Shared SmartPlant Review Station
 - Over the fence Engineering and Procurement



The impact per \$Billion / Year

- Delta between the Best and the Worst
 - 38 – 45.1 Direct Activity = 7.1%
 - 7.1/40 is a **17.8%** increase in Productivity
 - 17.8 % of \$400 Million (the construction portion of the TIC)
= **71.2 \$Million** cost reduction/\$Billion
+ **65 days** of schedule per year
- Cost of implementation is about 2% (1-50)
ROI > 900%

This is based on only 77% compliance.



- World class Safety Performance
- Minimal Punch Lists
- Reduced Indirects (Document Control, Project Controls, Material Management)
- Best in Class Scaffold Performance (18% of Direct)



Any
Questions